Notification, dated 1st February 1897.

Mr. C. Narayana Rao, Acting Amildar and 3rd Class Magistrate of Tirthal Section 37 of the Code of Criminal Procedure, invested with the following powers :—

(1) Power to make orders prohibiting repetitions of nuisances, Section 143.
(2) Power to make orders under Section 144.
(3) Power to hold inquests, Section 174.
(4) Power to take cognizance of offences upon complaint, Section 191.
(5) Power to take cognizance of offences upon police reports, Section 191.
(6) Power to try offences under the Excise Act.

B. K. VENKATAVARADAIENGAR, *Dt. Ma*

...li taluk, is, under

MYSORE DIVISION.

The 28th January 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore division, up to 11th February 1897, for improving the Tirumakudlu-Narsipur-Chamrajnagar road, T.-Narsipur taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1899, but during this year progress of Rs. 3,000-0-0 must be shown.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Engineer and accompanied by a statement, in the form given below, showing the ra the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred Promissory Notes, as earnest money, and be superscribed "Tender for impro Narsipur-Chamrajnagar road, T.-Narsipur taluk" ; in default of which, ten

5. The final acceptance of any tender will rest with the Chief Engineer, w self to accept the lowest or any tender, or to assign any reason whatever for tender.

6. Within eight days of the acceptance of the tender, the successful competito to execute the usual contract bond ; in default of which his tender will be consider his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be p notice board in the Executive Engineer's office in due course. No enquiries regarding the or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will

ABSTRACT.

Items.					*Per.*	*Quanti*
Collections of materials—						
Collection of gravel, excavating stocking and carriage up to one furlong	..	..	..	..	C. yd.	
Carriage of gravel ½ mile lead	..	..	..	..	,,	
Do ⅝ do	..	..	..			
Do ⅝	..	..	..			
Do ¾	..	..	..			
Do ⅞	..	..				
Do 1⅛						
Do 1¾						
Do 2¾						
Consolidation of materi						
Picking the road surface						
Spreading, watering an						
Removal of top soil fro						

Notice is hereby given
Mysore division, up to 11
road, Chamrajnagar taluk.
are not guaranteed. The

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving Tirumakudlu-Narsipur-Chamrajnagar road, Chamrajnagar taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Items.	*Per.*	*Quantity.*	*Rate.*
Collection of materials—			
Collecting and stocking gravel up to 1 furlong lead	C. yd.	20,292	
Carriage of gravel $\frac{1}{8}$ mile lead	,,	1,212	
Do $\frac{1}{4}$ do	,,	1,649	
Do $\frac{3}{8}$ do	,,	1,128	
Do $\frac{1}{2}$ do	,,	751	
Do $\frac{5}{8}$ do	,,	1,241	
Do $\frac{3}{4}$ do	,,	1,142	
Do $\frac{7}{8}$ do	,,	1,464	
Do 1 do	,,	1,393	
Do $1\frac{1}{8}$ do	,,	1,294	
Do $1\frac{1}{4}$ do	,,	1,250	
Do $1\frac{3}{8}$ do	,,	757	
Do $1\frac{1}{2}$ do	,,	275	
Do $1\frac{5}{8}$ do	,,	275	
Do $1\frac{3}{4}$ do	,,	263	
Do $1\frac{7}{8}$ do	,,	275	
Do 2 do	,,	275	
Do $2\frac{1}{8}$ do	,,	275	
Do $2\frac{1}{4}$ do	,,	275	
Do $2\frac{3}{8}$ do	,,	275	
Do $2\frac{1}{2}$ do	,,	275	
Do $2\frac{5}{8}$ do	,,	238	
Do $2\frac{3}{4}$ do	,,	275	
Do $2\frac{7}{8}$ do	,,	238	
Do 3 do	,,	275	
Do $3\frac{1}{8}$ do	,,	256	
Do $3\frac{1}{4}$ do	,,	275	
Do $3\frac{3}{8}$ do	,,	263	
Do $3\frac{1}{2}$ do	,,	275	
Do $3\frac{5}{8}$ do	,,	263	
Do $3\frac{3}{4}$ do	,,	256	
Do $3\frac{7}{8}$ do	,,	275	
Do 4 do	,,	275	
Do $4\frac{1}{8}$ do	,,	275	
Consolidation of materials—			
Spreading and consolidating gravel	C. yd.	20,292	
Forming and rolling roads	Furlong.	*99	
Earthwork	C. yd.	7,810	
Turfing	Sqr.	262·90	
Dry stone work	C. yd.	183	
Slab stones	S. ft.	704	
Extending irrigation tunnels	Tunnel.	3	
Metalling with brick bats	Lump sum.		

*This item has been provided instead of picking, which is not necessary.

The 4th February 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore division, up to 20th February 1897, for constructing Lines for the Special Reserve Police in Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1898 and during this official year progress of (10,000) ten thousand rupees only must be shown.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for constructing lines for the Special Reserve Police in Mysore;" in default of which tenders will be rejected.

5. The first acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Items of work.	*Per.*	*Quantity.*	*Rate.*
Earthwork excavation	C. yd.	1,062	
Earth-filling	Do	1,035	
Concrete foundations	C. ft.	11,400	
Brick in chunam	Do	40,881	
Brick in clay	Do	65,460	
Archwork	Do	579	
Teak wood door battened	S. ft.	2,604	
Do windows do with ironbars	Do	321	
Do pannelled and glazed with bars	Do	90	
Do ventilators	Do	432	
Slab stones	Do	3,658	
Teakwood work wrought and put up	C. ft.	1,907	
Pucka terracing with brick on edge and flat tiles, &c. ..	Sqr.	3·09	
Terracing do and concrete over	Do	6·05	
Roofing with teak reapers and 1st class Mangalore tiles ..	Do	332·16	
Bengal terracing	Do	15·01	
Ridge tiles including fixing	R. ft.	963	
Ventilating tiles	Each.	162	
Cornice work	R. ft.	141	
Plaster moulding	Lump sum.		
Plain parapet wall	R. ft.	50	
Pediments with cornice and finials over windows of upper storey..	Each.	6	
Ornamental eaveboards	R. ft.	1,897	
Ornamental finials	Each.	6	
	Do	4	
Coping with brick in chunam	R. ft.	2,072	
Plastering with chunam	Sqr.	543·52	
Mud plastering	Do	734·85	
Gate door	Lump sum sqrs.		
Concrete flouring	Sqrs.	178·24	
Whitewashing two coats	Do	1,278·37	
Wood oiling two coats	Lump sum.		
Painting do	Sqrs.	120·04	
Gravelling	C. yd.	..	
Staircase	Lump sum.		
Levelling the ground and forming the road	Do		
Constructing V-shaped drains with granite slabs including			

The 4th February 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore division, up to 28th February 1897, for constructing Students' Home at Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1899, but during this year a progress of (6,000) six thousand rupees must be shown.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 750 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for constructing Students' Home at Mysore; in default of which, tenders will be rejected.

5. The first acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Items of work.	*Per.*	*Quantity.*	*Rate.*
Earthwork excavation	C. yd.	1,023	
Earth-filling to basement	,,	919	
Burnt brick in mortar	C. ft.	73,824	
Archwork	,,	2,626	
Plastering with chunam	Sqr.	816·22	
Teakwood work wrought and put up	C. ft.	1,451	
Roofing with first class Mangalore tiles, teak reapers 2" × 1" &c., complete	Sqr.	192·27	
Terracing with terrace brick on edge and finished off with concrete and two courses of flat tiles, &c., complete	,,	40·07	
Ridge tiles set in mortar	R. ft.	764	
Heavy cornicing including brickwork, &c., complete	,,	804	
String course	,,	357	
Ornamental parapets, complete	,,	324	
Teakwood pannelled doors with brass hinges, locks, &c., complete	S. ft.	649	
Teakwood windows with pannelled shutters outside glazed shutters inside fitted ¾" iron bars, complete	,,	429	
Teakwood ventilators with ropes, complete	,,	160	
Do circular do	,,	106·84	
Burnt stone slabs edges chisled, dressed and fitted	C. ft.	821	
Burnt stone pavement edges dressed and joints pointed with asphalt	Sqr.	49·90	
Concreting, including smoothening	C. ft.	3,910	
Wood oiling two coats	Sqr.	108·96	
Painting with Carson's light blue, two coats	,,	70·75	
Color and whitewashing, two coats	,,	816·22	
Teakwood ornamental eaveboards 12" wide	R. ft.	165	
Do do 9" wide	,,	1,090	
Finials ornamental	Each.	14	
Levelling ground and laying out roads	Lump sum.		
Burnt brick in clay	C. ft.	8,871	
Teakwood battened doors complete	S. ft.	414	
Do do windows with iron bars	,,	280	
Teakwood eaveboards plain	R. ft.	544	
Zinc valleys	S. ft.	250	
Drain under basement to lead off water from sink	Lump sum.		
Coping with brick in chunam complete	R. ft.	850	
Galvonized iron tubs	Each.	18	
Honnewood battened doors complete	S. ft.	176	
Painting with chocalate two coats	Sqr.	4·80	
Ornamental capitals to wicket-gate pillars	Lump sum.		
Wicket-gate complete with hooks, &c.	S.ft.	27	

V. H. KARVE, *Executive Engineer.*